

GOVERNMENT OF TAMILNADU PUBLIC WORKS DEPARTMENT WATER RESOURCES ORGANISATION

Region: Trichy Circle: Middle Cauvery Basin, Trichy

Marudaiyaru Basin Division, Ariyalur.

ANAIVARI ODAI SUB BASIN

Additional Proposals for Providing Lining in head Irrigation Channel and Flow Measuring Device in Anaivari Odai Sub Basin (Phase II) under IAMWARM Project.

Estimate Amount Rs. 58.82 Lakh

INDEX

SI No	DESCRIPTION	PAGE
1	REPORT	1
2	FORMAT I	2
3	FORMAT II	3
4	INDEX MAP	4
5	SUB BASIN MAP	5
6	DRAWINGS	6-8

Additional Proposals for Providing Lining in head Irrigation Channel and Flow Measuring Device in Anaivari Odai Sub Basin (Phase II) under IAMWARM Project

The lining in head irrigation channel and installation of measuring device has been proposed for Phase I and II sub basins by utilizing the Project Savings as discussed with the world bank, during the implementation support mission from Sept 12-20 th 2011

Accordingly in Anaivari Odai sub basin of Phase II the following works have been proposed

- 1. Lining in head irrigation channel below the tanks sluice using C.C. M15 as per sketch enclosed.
- 2. Installing flow measuring device in the irrigation channel as per sketch
- 3. L.S.provision of 2.80 % for provision of labour welfare @ 0.30 % and provision for Contingencies, advertisement charges, Photographic charges @ 2.50 %

The Package details are appended separately and works are proposed to be taken up under National Shopping Procedure.

The total cost for the DPR works out to Rs.58.82 Lakh.

FORMAT-

Ι

Name of Region Trichy

Name of Circle Middle Cauvery Basin Circle, Trichy.

Marudaiyaru Basin Division,

16

Name of Division Ariyalur.

Name of Sub

Basin Anaivari Odai
Total Number of Tanks taken up under

IAMWARM:

NO OF TANKS, SLUICES IN EACH PACKAGE

TOTAL NO OF TANKS TAKEN UNDER IAMWARM: 16 Nos Rs. in Lakh

SI No	Package No	Name of Tank	No of Sluice	Flow Measuring Device		Lining in head irrigation channel			Total	L.S.Provision	Grand	Remarks
				No	Amount	Type of soil BC/OS	Length in Metre	Amount	Amount	@2.80%	Total	Remarks
1	2	3	4	5	6	7	8	9	10	11	12	13
	Package-1	Rayampuram Periya eri	2	2	0.20	ВС	100	3.20	3.40			
1		Nakkampadi periya eri	2	2	0.20	ВС	100	3.20	3.40			
		Sendurai Periya eri	3	3	0.30	ВС	120	3.84	4.14			
		Total	7	7	0.70		320	10.24	10.94	0.31	11.25	
	Package-2	Nakkampadi pudu eri	1	1	0.10	ВС	30	0.96	1.06			
2		Nallanayagapuram periya eri	2	2	0.20	ВС	100	3.20	3.40			
		Kulumur periya eri	4	4	0.40	ВС	120	3.84	4.24			
		Total	7	7	0.70		250	8.00	8.70	0.24	8.94	
	Package-3	Ettikulam Tank	1	1	0.10	ВС	50	1.60	1.70			
		Namankunam Tank	1	1	0.10	ВС	50	1.60	1.70			
3		Veeravasi eri	1	1	0.10	ВС	50	1.60	1.70			
		Alagu padaiyachi nanthian kuttai	2	2	0.20	ВС	100	3.20	3.40			
		Chitheri(Mathur)	2	2	0.20	ВС	100	3.20	3.40			

		Total	7	7	0.70		350	11.20	11.90	0.33	12.23	
4	Package-4	Thalavai periya eri	4	4	0.40	ВС	120	3.84	4.24			
		Neelampuram Tank	3	3	0.30	ВС	150	4.80	5.10			
		Total	7	7	0.70		270	8.64	9.34	0.26	9.60	
5	Package-5	Thalavai Echankatu eri	4	4	0.40	ВС	160	5.12	5.52			
		Thathanur Pudu eri	4	4	0.40	ВС	160	5.12	5.52			
		Total	8	8	0.80		320	10.24	11.04	0.31	11.35	
6	Package-6	Thathanur Periya eri	5	5	0.50	ВС	150	4.80	5.30			
		Total	5	5	0.50		150	4.80	5.30	0.15	5.45	
	GRAND TOTAL			41	4.10		1660	53.12	57.22	1.60	58.82	_

Certified that the Tanks included in the originally approved in Anaivari Odai Sub Basin DPR alone are considerded now Certified that the above works have not been taken up in any other Project

Certified that the field/Irrigation channel drawing type I is adopted in Number of Tanks having soil other than black cotton soil

BC - Black Cottan soil

Certified that the field/Irrigation channel drawing type II is adopted in 16 Number of Tanks having black cotton soil

OS- Other Soil

FORMAT II

Name of Region Trichy

Name of Circle Middle Cauvery Basin Circle, Trichy.
Name of Division Marudaiyaru Basin Division, Ariyalur.


Name of Sub Basin Anaivari Odai Total Number of Tanks taken up under IAMWARM : 16

Method of procurement : National shopping


(Note: Procurement plan to be got approved by World Bank separately)


PACKAGE WISE ABSTRACT

SI. No	Package No.	Name of Work	Lining Length (M)	No of Flow Measuring Devices	No. of Tanks	Total Amount including L.S. (Rs. In Lakhs)	Remarks
1	2	3	4	5	6	7	8
1	AP_1/ IAMWARM/ WRD/ AVO/ WORKS/ II / 2011-2012	Lining in head irrigation channel and providing Flow Measuring devices for Rayampuram Periya eri, Nakkampadi periya eri, Sendurai Periya eri in Anaivariodai Sub basin in Ariyalur District	320	7	3	11.25	
2	AP_2/ IAMWARM/ WRD/ AVO/ WORKS/ II / 2011-2012	Lining in head irrigation channel and providing Flow Measuring devices for Nakkampadi pudu eri, Nallanayagapuram periya eri, Kulumur periya eri in Anaivariodai Sub basin in Ariyalur District	250	7	3	8.94	
3	AP_3/ IAMWARM/ WRD/ AVO/ WORKS/ II / 2011-2012	Lining in head irrigation channel and providing Flow Measuring devices for Ettikulam Tank, Namankunam Tank, Veeravasi eri, Alagu padaiyachi nanthian kuttai, Chitheri(Mathur) in Anaivariodai Sub basin in Ariyalur District	350	7	5	12.23	
4	AP_4/ IAMWARM/ WRD/ AVO/ WORKS/ II / 2011-2012	Lining in head irrigation channel and providing Flow Measuring devices for Thalavai periya eri, Neelampuram Tank in Anaivariodai Sub basin in Ariyalur District	270	7	2	9.60	
5	AP_5/ IAMWARM/ WRD/ AVO/ WORKS/ II / 2011-2012	Lining in head irrigation channel and providing Flow Measuring devices for Thalavai Echankatu eri, Thathanur Pudu eri in Anaivariodai Sub basin in Ariyalur District	320	8	2	11.35	
6	AP_6/ IAMWARM/ WRD/ AVO/ WORKS/ II / 2011-2012	Lining in head irrigation channel and providing Flow Measuring devices for Thathanur Periya eri in Anaivariodai Sub basin in Ariyalur District	150	5	1	5.45	
		TOTAL	1660	41	16	58.82	




Sub Basin Map (Tanks) DETAILS OF TANKS, ANIGUTE,





LINING OF IRRIGATION CHANNEL TYPICAL CROSS SECTION



(MADURAL PART)